


**International Centre for Theoretical Sciences
Tata Institute of Fundamental Research**

Name of work: Supply and fixing book shelf for Library at ICTS-TIFR campus, Shivakote village, Bengaluru.

Schedule of Quantities

Sl No.	Description	Unit	Qty	Rate	Amount
1	Providing and fixing modular book shelf, Linear work table and under/above counter storage boxes etc., for the following (With open and close type) at all heights in all floors etc., using 19 mm approved quality marine plywood as per latest revision of IS710 of M/s. Kit ply/M/s.Century/M/s. Greenlam for all-round boxing, shutter, shelves and frame with approved colour and make 1mm thick laminate of approved shade (Sahara walnut of M/s Associate) for all exposed cut surfaces and 0.8 mm thick laminate for all un exposed areas /internal surface, properly framed and jointed, including labour charges approved brand hardware's, locking arremment,etc complete, including cost of labour for fixing building hardware etc., complete as per specifications and drawing.				
	including providing and fixing edge binding for book shelf 1mm thick of M/s Rehau or M/s LG or equivalent PVC lipping of suitable width for all cut surfaces or exposed cut edges, wooden plugs, SS star headed screws, nails, etc., complete with all lead and lift. Note : 1.Measurement will be taken for elevation area only for payment. 2. All furniture's shall be modular type with customised to sizes as per the actual dimension available at site for each unit. 3. Quoted rate shall be inclusive of all fittings & fixtures/ accessories & wastages. 4. Quoted rate shall hold good for furniture's of all shapes & sizes in straight/curvilinear and any geometric shape.5. Included bookshelf image is indicative for typical open book shelf.				
	Book shelf approximate size of each is 2950mm (L) x 2800mm(H) x 380mm (D)	Sqm	134.00		
				Total Rs.	



- Note:**
1. Rate inclusive of all WCT, Labour cess, Service tax and other applicable taxes if any.
 2. Front elevation shall be considered for payment up to two decimals. Shelves, intermediate support/partition will not be measured separately for payment.
 3. Water and electricity will be provided by department free of cost.
 4. Quoted rate shall be inclusive of removing all debris generated and disposing at a designated place as per the statutory authorities.
 5. Damage to any existing Structure & installations shall be restored back without any cost to department.
 6. No extra payment will be made for minor dismantling works like, plaster, brickwork, concrete and masonry.
 7. Quoted rate shall be inclusive of transportation, all leads & lifts, necessary fittings & fixtures, S.S screws etc.,
 8. Any damage/ dents is found in the furniture, same shall be liable for rejection.
 9. All ply shall be of approved make of IS 710 BWP/BWR.
 10. All fittings and fixtures shall be of approved make of M/s Ebco, M/s Dorma, M/s Hettich, M/s Hafele, M/s Ozone, M/s Enox.

(Total Rupees)

Contractor's Seal with Signature